

JOINT USE

DRAWING NUMBER	SHT.	DRAWING TITLE	DWG REV.	BOM REV.
B-28-01	1 - 2	RESIDENTIAL JOINT-USE TAKE-OFF	C	C
B-28-02	1 - 1	COMMUNICATION TAKE-OFF ON JOINT USE POLE (TYPICAL)	0	-
B-28-05	1 - 1	CONDUCTOR DEPTH OF COVER (REFER TO B-14-65)	B	-

SaskPower - DISTRIBUTION STANDARDS

APPROVAL

L. MOEN

DESIGN CHK

A. UHREN

DRN. **ARU**

CHKD.

2016-06-28

INDEX

DATE OF ISSUE: 2016/07/26

DRAWING NO: **B-28-INDEX**

SHEET 1 of 1

REV. G

BILL OF MATERIAL


ITEM NO.	CODE NO.	QUANTITY		DESCRIPTION
		A	B	
1	1 34 08	-	3	GUARD CABLE PLASTIC – 4" x 8'
1	1 34 09	3	-	GUARD CABLE PLASTIC - 2 1/2" x 8'
2	1 34 10	-	1	GUARD CABLE STEEL - 4" x 8'
2	1 34 11	1	-	GUARD CABLE STEEL - 2 1/2" x 8'
3	1 78 38	6	6	SCREW LAG – 1/2" x 4"
4	5 09 10	3	3	CONNECTOR COMPRESSION
5	5 46 18	2	2	STRAP LEAD
6	7 69 62	.30	.30	SCREW WOOD - #10 – 1 1/2" (100/BOX)
7	5 646 582	2	2	DECAL – WATCH FOR WIRES

NOTE:

1. USE COLUMN 'A' OR 'B' TO SUIT THE NUMBER OF CIRCUITS. COLUMN 'A' – 2-1/2" CABLE GUARD, COLUMN 'B' – 4" CABLE GUARD.

SaskPower - DISTRIBUTION STANDARDS

DRN.	DESIGN CHK.	APPROVAL	SECONDARY TAKE-OFF STRUCTURE
CHKD.			
DATE	DATE	DATE	
DATE OF ISSUE 2007/04/16		DRAWING NO: B-28-01	SHEET 1 OF 2 REV. C




1. TRENCH TO BE IN LINE WITH O.H. CONDUCTOR MINIMUM 1.2m
2. THE GROUND IS REQUIRED WITH A TRANSFORMER INSTALLATION.
3. MAXIMUM IS FOUR UNDERGROUND RESIDENTIAL SERVICES.
4. SASKTEL/CATV CHARGES, FLAT RATE/ SERVICE IN NATURAL EARTH, ARE SHOWN IN FORM I.
5. USE B-14-11 FOR NEW CONSTRUCTION.

SCALE: N.T.S. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE INDICATED

SaskPower – DISTRIBUTION STANDARDS

DRN.	DESIGN CHK.	APPROVAL	RESIDENTIAL SERVICE JOINT USE TAKE-OFF
CHKD.			
DATE 92-11-24	DATE	DATE	
DATE OF ISSUE: 2007/04/16	DRAWING NO. B-28-01	SHEET 2 of 2	REV. C



NOTES:

1. POLE TO BE ARRANGED IN 4 QUADRANTS.
2. NEED TO MAINTAIN 1/2 OF POLE(2 QUADRANTS) CLEAR FOR CLIMBING,ADJACENT TO ALLEY.
3. COMMUNICATION TAKE-OFF TO BE ADJACENT TO QUADRANT WITH SASKPOWER TAKE-OFF.
4. COMMUNICATION TAKE-OFF NOT TO BE LOCATED UNDER TRANSFORMER OR CUTOUT.
5. UNDERGROUND CABLE TAKE-OFF SHALL BE IN LINE WITH OVERHEAD CIRCUIT FOR 1.2m TO AVOID POLE LEANING.
6. POLES DRAWN SHOWING VIEW FROM HOUSE SIDE.

SaskPower - DISTRIBUTION STANDARDS

DRN.	DESIGN CHK.	SAFETY APP.	APPROVAL	COMMUNICATION TAKE-OFF ON JOINT USE POLE (TYPICAL)
CHKD.				
DATE	DATE	DATE	DATE	
DATE OF ISSUE: 2007/04/16			DRAWING NO. B-28-02	SHEET 1 of 1
				REV. 0